

REFERENCE			
NUMBER	DESCRIPTION	QUANTITY	SIZE
1	METER BASE	1	FURNISHED BY COOP
2	EXPANSION SLEEVE	1	FURNISHED BY COOP
3	CONDUIT RIGID OR SCHEDULE 40 PVC	12 FT	3"
4	CONDUCTOR	AS REQUIRED	250 MCM COPPER
	OPTIONAL (ALUMINUM)	AS REQUIRED	500 MCM ALUMINUM
	OPTIONAL (COPPER)	AS REQUIRED	(2) 3/0 COPPER
	OPTIONAL (ALUMINUM)	AS REQUIRED	(2) 4/0 ALUMINUM
5	CONDUIT STRAP	4	3"
6	LAG SCREW	12	AS REQUIRED
7	COPPER GROUND ROD	1	5/8" X 8'
8	GROUND ROD CLAMP	1	5/8"
9	WEATHERPROOF DISCONNECT	1	400 AMP
10 TREATED LUMBER OR ALUMINUM STRUT		AS REQUIRED	AS REQUIRED
11	TREATED 4X4 POST OR ALUMINUM POSTS	2	8'
12 BUSHING, INSULATING		2	3"
13	GROUND CONDUCTOR	AS REQUIRED	1/0 COPPER
14	BUSHING, BONDING TYPE	4	3"
15	GALVANIZED LOCKNUT	8	3"
16	SCREWS	8	AS REQUIRED
17	MAIN BREAKER OR FUSE	1	400 AMP
18	CONDUIT NIPPLE	1	3"

	400 AMP UNDERGROUND SERVICE						
	METER ON PEDESTAL SINGLE DISCONNECT						
TRI-COUNTY ELECTRIC COOPERATIVE							

Date: Drawn By: Reviewed By:			
	Date:	Drawn By:	Reviewed By:
	1/16/2023	MVB	ENG DEPT